


**Sampling Survey Results of  
Unit 3 Trench Vertical Shaft A at  
Fukushima Daiichi Nuclear Power Station**

**July 11, 2013**

**Tokyo Electric Power Company**

# Sampling Survey Method of Unit 3 Vertical Shaft A




- Investigated on July 10, 2013
- Analyzed on July 11, 2013
- Water was sampled by a vacuum water sampler
- Sampled at 3 points categorized by water depth (Water depth: Approx. 1, 7, 13m)
- Radiation exposure dose = 0.49mSv/person

Vertical shaft A of Unit 3

# Sampling Survey Results

## ■ Analysis results of the main $\gamma$ nuclides



Location (water depth)	Saline (ppm)	Cs134 (Bq/cm <sup>3</sup> )	Cs137 (Bq/cm <sup>3</sup> )	Remarks
① ( 1m)	11,000	5.0 x 10 <sup>4</sup>	1.0 x 10 <sup>5</sup>	I-131 and Co-60 was both ND (<From 10 <sup>2</sup> )
② ( 7m)	7,500	3.4 x 10 <sup>4</sup>	6.9 x 10 <sup>4</sup>	Same as above
③ (13m)	7,000	3.1 x 10 <sup>4</sup>	6.2 x 10 <sup>4</sup>	Same as above

Vertical shaft A of Unit 3

# Condition of the Seawater Piping Trench at Units 1-4

- Contaminated water at Unit 2 and 3 is flowing into the trench. We will consider measures to prevent the inflow immediately.
- Water level of the Turbine Building (T/B) is changing according to that of the trench vertical shaft as well as the densities at Unit 2.
- There are some time lag of water level change between the Turbine Building (T/B) and the vertical shaft at Unit 3.  
(It is estimated to be the way of connection between the Turbine Building (T/B) and the vertical shaft is different at Unit 2 and Unit 3.)

	Density of contaminated water (Cs137)		Ambient dose	Bottom location of the trench	Remarks
	T/B	Trench			
Unit 1	From 10 <sup>4</sup> Bq/cm <sup>3</sup>	From 10 <sup>1</sup> Bq/cm <sup>3</sup>	-	OP-12M	Note 1
Unit 2	From 10 <sup>4</sup> Bq/cm <sup>3</sup>	From 10 <sup>4</sup> Bq/cm <sup>3</sup>	Approx. 10mSv/h	OP-12M	Note 2
Unit 3	From 10 <sup>4</sup> Bq/cm <sup>3</sup>	From 10 <sup>5</sup> Bq/cm <sup>3</sup>	Approx. 100mSv/h	OP-17M	Note 3
Unit 4	From 10 <sup>4</sup> Bq/cm <sup>3</sup>	From 10 <sup>2</sup> Bq/cm <sup>3</sup>	Approx. 1mSv/h	OP-1M	Note 4

Note 1: The trench is connected to the ground surface of T/B at Unit 1. Therefore, there is no inflow of contaminated water into the seawater trench.

Note 2: Densities of contaminated water of T/B is equivalent to that of the trench at Unit 2 (sampled from the vertical shaft at T/B side).

Note 3: Ambient dose inside the trench (vertical shaft at T/B side) is high at Unit 3. → Highly contaminated water was diluted slightly which was measured at this time.

Note 4: The trench is located in T/B side, and is erected vertically from the underground floor to the ground surface at Unit 4. Therefore, there is no inflow of contaminated water into the seawater trench.

# (Reference) Overview of the Seawater Piping Trench at Unit 3 and 4

Referred from the Mid-and-long-Term Roadmap announced on June 27.

