

## 1. Decrease of water level inside the dike in advance

- Water level inside the dike will be lowered in advance by transferring water to 4,000m<sup>3</sup> notch tanks and the underground reservoir.

## 2. Securement of Capacity of 4,000m<sup>3</sup> notch tanks

- Water stored in 4,000m<sup>3</sup> notch tanks will be discharged to Unit 2, 3 Turbine Buildings in order to secure capacity of the notch tanks.


## 3. Enforcement of transfer facilities and increase of transfer capability

- Area where radiation level inside the dike is high: Transfer facilities (pump, hose and fire engine) will be enforced.
  - Pump: 60m<sup>3</sup>/h x 19, hose: 75mm in diameter (total length:6km), fire engine: 5  
[Target area: H1-East, H2-South, H2-North, H3, H4, H4-North, H4-East, H5, H6]
  - Area where radiation level inside the dike is intermediate: Following vehicles used to transfer water to 4000m<sup>3</sup> notch tanks, underground reservoirs will be added: Large-sized suction vehicle (3 (20m<sup>3</sup>)→6 (46m<sup>3</sup>)), 3 tank trucks (30m<sup>3</sup>), 1 fire engine  
[Target area: B-South, G6-South]
  - Area where radiation level inside the dike is low: Water will be temporarily stored in the notch tank, and will be discharged after analysis.
    - \* Water will be sampled directly from the dike, and will be discharged after analysis in case of heavy rain.  
[Target area: B-North, C-East, C-West, E, H8-North, H8-South, H9, H9-West, G3-North, G3-East, G4-South, G6-North]


## 4. Increase of capacity of rainwater receiving tank

- Rainwater receiving tank was installed near H2 area (500m<sup>3</sup> sized tank x 1).

# Overview of Transfer Facilities for Accumulated Water inside the Dike



# Enforcement of Transfer Functions for Accumulated Water inside the Dike



# Precautionary Measures against Typhoon and Heavy Rainfall

(\* Area where Water inside the Dike Exceeded Discharge Standard)

